BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 Indent No.20427

SCHEDULE-B

NAME OF WORK: Providing street name board at AGB layout, Babanna layout and Medarahalli in W.no.12 Shetty halli Sub division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor N THIPPESWAMY		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	7
1	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specfication & as per direction of Engineer-in-charge	Cum	33.12	85.0	Rupees Eighty Five Only	2815.20
2	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km complete as per specfication & as per direction of Engineer-in-charge	Cum	33.12	80.0	Rupees Eighty Only	2649.60
3	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregares @ 0.465 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specfication & as per direction of Engineer-in-charge	Cum	8.28	5000.0	Rupees Five Thousand Only	41400.00
	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specfication & as per direction of Engineer-in-charge	Cum	24.84	6000.0	Rupees Six Thousand Only	149040.00

nature of the Contractor

Executive Engineer

5	Supplying of MS steel name boards as per approved design and specification complete with all leads and lifts as per the direction of the Engineer-in-charge of the work (Data rate approved) complete as per specfication & as per direction of Engineer-in-charge	Nos	115	4300.0	Rupees Four Thousand Three Hundred Only	494500.00
6	Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications	Sqm	120.29	80.0	Rupees Eighty Only	9623.20
7	Applying red lead ready mix priming coat over new steel or other metal surface including preparing the surface after thoroughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, laour complete as per specfication & as per direction of Engineer-in-charge	Sqm	120.29	30.0	Rupees Thirty Only	3608.70
8	Painting new letter and figures of any shade with synthetic enamel paint black or nay other approved colour to give an even shade complete as per specifications ("ii) Hindi (Matras commas and the like not to be measured and paid for half letter shall be counted as half) complete as per specfication & as per direction of Engineer-in-charge	cm	237000	0.7	Seventy Paise Only	165900.00
					Total	869536.70
					Percentage	-12.16%

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

ignature of the Contractor

Executive Engineer